

**MOMBASA REGION** 

## ADDENDUM NO.1

## ADDENDUM TO THE TENDER NOTICE

26th FEBRUARY, 2019

The Authority through the Regional Manager Mombasa invited bids from eligible registered **contractors** in F/Y 2017/19 in the respective constituency and category: Women, Youths and Persons with Disability Registered by National Treasury to submit bids for spot improvement of various **works:** -

• The scope of Works in the BQ for Road P514\_Mombasa: Marimani Nursery School-Marimani Primary School. Contract No. KeRRA/011/MSA/39/034/2018/2019 in Kisauni Constituency has been changed as per the attached Bill of Quantities.

NOTE: ALL OTHER DETAILS STATED IN THE ADVERTISEMENT NOTICE REMAINS UNCHANGED

Mr.GilbertKimaiyo
For:DeputyDirector.Roads
KeRRA - Mombasa Region

contract KeRRA/011/MSA/39/034-

Name 18|19

## **BILL OF QUANTITIES**

**Activity Group Title** 

## 2018-19

P514\_Mombasa

Marimani Nur Sch-Marimani

Contractor 0 Primary School

Contractor		<u> </u>		Filliary School		
Bill No.	ITEM CODE	DESCRIPTION	Quantity	UNIT	Unit Bid RATE (KShs)	Bill Item Cost without VAT (KSHs)
1	01-50-014	Field supervision	1.00	KS	300,000.00	300,000.00
1	01-50-016	Materials Investigation &Testing	1.00	KS	30,000.00	30,000.00
1	01-80-016	Provide and erect publicity signs as directed by the Engineer	1.00	NO.	25,000.00	25,000.00
4	04-50-003	Heavy Bush Clearing	8,664.68	$M^2$		
4	04-50-008	Clearing obstructions (boulders & debris)	1.00	KS		
5	05-50-004	Excavation to Level & Compaction	199.00	М³		
5	05-50-007	Fill in hard material and compact	189.26	М³		
7	07-50-001	Excavate for structure in soft material	210.00	М³		
7	07-60-025	Provide and place macafferri or equivalent 2x1x1 m gabions and matresses as shown on the drawings or as directed by the Engineer.	425.31	M <sup>2</sup>		
7	07-60-094	Provide and place rock fill to gabion boxes	60.00	М³		
20	20-50-012	Kerbs	210.00	MT		
10	10-50-002	Heavy grading with watering and compaction instructed by the Engineer	8,000.00	M³		
12	12-50-001	Provide, lay and compact Hand packed stone material including fillings voids with stone dust as directed by the Engineer.	152.00	М³		
12	12-50-002	Provide, place, spread and compact natural gravel for subbase	400.00	M³		
23	23-50-001	Concrete blocks pavement	550.00	M <sup>2</sup>		
		Sub Total				
		Contingencies @ of 0%				
		Total				
		VAT @ 16%				
		Grand Total				